

SURVEY & REMONUMENTATION

MAR 04 1998

SECTION

1997 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>27</u> N R <u>7E</u> | <u>C-10</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

APPROVED LAND CORNER
P.A. 345 of 1990
ALCONA COUNTY

Date 7/30/97

County Rep. D. B. Tom

RECORDED

Date 10-31-1997

REMON LIBER 1 PAGE 267

Time 3:30 P.M.

Doris A. Gauthier
Doris A. Gauthier
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on April 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: GLO Survey by Lewis Clason - set 1/4 post, referenced: Maple 8 - S 74 E - 21 / Y. Pine 16 - N 65 W - 13.
- 1906: County Survey by Edw. Chapelle - fd. post.
- 1911: County Survey by Andrew J. Freer - fd. gray boulder 6'x11'x14' w/ cross on top w/ glass.
- 1920: County Survey by Andrew J. Freer - fd. gray boulder 6'x11'x12' glass and dishes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Fd. R.R. spike 3' East of centerline

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997: Placed 3" Alcona County cap stamped to identify the corner over 1/2" iron rod in monument box.
Referenced:
N69°E - 42.39' - set tag in post
S62°E - 37.49' - fd. spike in 28" White Pine
S53°W - 43.28' - set tag in 5" Poplar
N63°W - 39.68' - set tag in 10" Birch

Signed by *Daniel T. Kibbe*
Surveyor's Michigan License No. 37278

Date October 22, 1997

