

SURVEY & REMONUMENTATION

MAR 04 1998

SECTION

1997 Alcona County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27</u> N R <u>7</u> E	C-11
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

APPROVED LAND CORNER
 P.A. 345 of 1990
 ALCONA COUNTY

Date 7/30/97
 County Rep. Doris A. Gauthier

RECORDED

Date 10-31-1997
 REMON LIBER 1 PAGE 268

Time 3:30 PM
Doris A. Gauthier
 Doris A. Gauthier
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on April 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1838: GLO Survey by Lewis Glason - set post, referenced: Sugar 14 - S 56 E - 04 / Cedar 13 - N 43 W - 82.
 - 1902: County Survey by Edw. Chapelle - fd. stake, referenced: Sugar 14 - S 56 E 04 / Cedar 13 - N 43 W - 82.
 - 1906: County Survey by Edw. Chapelle - fd. gray boulder 9 x 12 glass under it, referenced: W. Pine Stump 20 - S 44 E - 69 / W. Pine Stump 21 - S 55 W - 81.
 - 1911: County Survey by W.S. Freer - corner reestablished from old Gov. corner by County Surveyor. Established 2 x 2 pine stake, 1 foot long.
 - 1916: County Survey by Andrew J. Freer - Set iron pin 21" long 1" dia., witness piece of boulder 19 x 11 x 5 - S 67 W - 58.
 - 1920: County Survey by Andrew J. Freer - fd. iron post.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1997: Fd. 1/2" rebar in centerline of road on fence line West.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1997: Placed 3" Alcona County cap stamped to identify the corner over 1/2" iron rod in monument box.
 Referenced:
 West 36.45' - set tag in post
 S15°E - 80.16' - set tag in 4" Twin Poplar
 N42°W - 62.49' - set tag in 6" Spruce
 N31°W - 87.56' - set tag in 8" Spruce

Signed by *Daniel T. Kibbe*
 Surveyor's Michigan License No. 37278

Date October 22, 1997

