

**SURVEY & REMONUMENTATION**

MAR 04 1998

**SECTION**

1997 Alcona County Remonumentation Corner  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

**APPROVED LAND CORNER**  
 PPA 3345 of 1990  
 ALCONA COUNTY

Date 7/30/97  
 County/Twp. Del. B. Town

**RECORDED**  
 Date 10-31-1997

**RENUMBER** 1 **PAGE** 265  
*Timothy J. Gauthier*  
**Doris A. Gauthier**  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27NR 7E</u>	<u>I-13</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Daniel T. Kibbe, in a field survey on June 11, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:**
- 1838: GLO survey by Lewis Clason - Set post, referenced Y. Pine 7-N45E-43 / Y. Pine 18-N59W-15.
  - 1911: County Survey by W.S. Freer - Fd. original corner 3X3 cedar stake.
  - 1913: County Survey by A.J. Freer - Orig. B.T. fd. reestablished corner.
  - 1920: County Survey by Andrew J. Freer - I-1 T26N-R7E Fd. gas pipe 37" long, 1 1/2" dia w/glass, Freer indicates common corners I-13 & I-1.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**
- 1997: Found 1/2" rebar at fence corner of fence lines South and West. This was accepted as I-1, T26N-R7E.  
 Established corner I-13 at recorded GLO distance East of I-1 27 links(17.82')
- This corner position is compatible with county and local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- 1997: PLaced 3" Alcona County cap stamped to identify the corner over 1/2" iron rod.  
 Referenced:  
 S29W-26.46'-Set tag in 4" maple  
 S65W-29.59'-Set tag in 10" twin maple  
 N13W-41.04'-Set tag in 8" oak  
 S62E-33.19'-Set tag in 12" maple  
 West-17.82'-Found 1/2" rebar, I-1, T26N-R7E  
 North-13.46'-Found 1/2" pipe

Signed by *Daniel T. Kibbe*  
 Surveyor's Michigan License No. 37278

Date October 22, 1997

