

SURVEY & REMONUMENTATION

MAR 04 1998

SECTION

1997 Alcona County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27</u> N R <u>7</u> E	<u>J-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

APPROVED LAND CORNER
P A 346 of 1990
ALCONA COUNTY

Date 7/30/97
County Rep. D. B. Green

RECORDED
Date 10-31-1997
REMON LIBER 1 PAGE 266

Time 3:30 M
Doris A. Gauthier
Doris A. Gauthier
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on June 11, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1838: GLO survey by Lewis Clason - Set 1/4 corner post, referenced: Spr. Pine 8-N15E-16 / Spr. Pine 7-N23W-15.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Found no evidence of original corner position. Established corner by single proportionate method. No good fence in area. Corner falls on East-West hunt wire and 20'± West of hunt wire to North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1997: Placed 3" Alcona County cap stamped to identify the corner over 1/2" iron rod.
Referenced:
S82W-17.01'-Set tag in 12" oak
N50E-18.96'-Set tag in 8" triple oak
S15W-34.95'-Set tag in 8" double oak
N40W-44.66'-Set tag in 8" oak.

Signed by *Daniel T. Kibbe*
Surveyor's Michigan License No. 37278

Date October 22, 1997

