

**SURVEY &  
REMONUMENTATION**

MAR 04 1998

**SECTION**

1997 Alcona County Remonumentation Corner  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED LAND CORNER  
P A 345 of 1990  
ALCONA COUNTY

Date 7/30/97  
County Rep. D. B. L.

RECORDED  
Date 10-31-1997

REMON LIBER 1 PAGE 271  
Time 3:30 P M  
*Doris A. Gauthier*  
Doris A. Gauthier  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Alcona  
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>27</u> NR <u>7E</u>	<u>L-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Daniel T. Kibbe, in a field survey on June 11, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1838: GLO survey by Lewis Clason - Set post, referenced: W. Pine 30-N65E-06 / Y. Pine - 28-N15W-19.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Found no evidence of original corner position except for 2 blazed poplar witness trees origin unknown. Established corner position using single proportionate method. This position is compatible with the two blazed witness trees and is considered to be a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

1997: Set 1/2" rebar and set 3" alcona County cap stamped to identify the corner, 23' South of Q of road.  
Referenced:  
S37E-14.26'-Set tag in blazed 14" poplar  
S62W-16.10'-Set tag in blazed 14" poplar  
N10E-42.40'-Set tag in 4" twin poplar  
N40E-58.58'-Set tag in 6" poplar

Signed by *Daniel T. Kibbe*  
Surveyor's Michigan License No. 37278

Date October 22, 1997

