

1993 Alcona County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Remon RECORDED
Liber 1 Page 5

DEC 17 1 45 PM '93

Handwritten signature: David A. Bantline
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

Form with fields: For corners in Alcona (County), Located In, Corner Code #, and numbered items 1-5 describing survey types and their locations.

Grid table with columns A-M and rows 2-13, containing numbers 1-36. A dot is present in the cell at row 10, column M.

I, Thomas L. Fabis in a field survey on November 19, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


- A. Description of original monument and accessories and/or subsequent restoration:
1838: G.L.O. Survey by Lewis Clason - set post (Y. Pine 10 S38°W 6, Y. Pine 6 N60°W 5)
1914: County Survey by Andrew Freer - Piece of Sleigh rave 32 in long 3: in wide 1/2 in thick 6 holes in it.
1976: L.C.R.C. Liber 1 Page 41 by Delmer Porter - Found 1" bar and established 3 witnesses (N67°E - 64.36' - 14" Oak, N68°W - 68.76' - 18" Norway, and S54°W - 85.91' - 18" Oak)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1993: Found 1" Bar and 2 witnesses (N67°E - 64.36' - 14" Oak, N65°W - 68.76' - 18" Norway) as per L.C.R.C.Liber 1 Page 41 and is accepted as a careful and faithful perpetuation of the position of the original corner.

SURVEY & REMONUMENTATION
1993
COMMISSION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1993: Removed existing corner material and set 5/8" iron rod with brass cap in Mon. Box during a Road Improvement Project for Alcona County Road Commission.

Reestablished witnesses are:
Set tag #31591 in 18" Oak - S29°E - 55.48'
Set tag #31591 in P. Pole - N52°W - 48.70'
Exis. tag in 16" Oak - N60°E - 64.36'
Exis. tag in 20" Norway - N68°W - 68.66'



Signed by Thomas L. Fabis Date November 24, 1993
Surveyor's Michigan License No. 31591