

1993 Alcona County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

<u>Alcona</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>7E</u>	M-11 (SE, 25) (Hawes Twp.)
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

DEC 17 1 45 PM '93

Janis A. Gauthier
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Thomas L. Fabis in a field survey on November 19, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: G.L.O. Survey by Lewis Clason - Set post (Y. Pine 10 S26W 12, W. Pine 8 N31°W 10)
- 1914: County Survey by Andrew Freer - Piece of Rail Road Iron.
- 1976: L.C.R.C. Liber 1 Page 41 by Delmer Porter - Found R.R. spike and established 3 witnesses (S45°W - 70.45' - power pole, S87°W - 51.00' - anchor pole, and S40°E - 53.07' - 8" W. Pine)
- 1976: L.C.R.C. Liber 1 Page 44 by John Oliver - Found R.R. spike and established 3 witnesses (S40° E - 8" White Pine - 53.15', S40°E - Conc. Mon. - 46.60', and N42°W - Power Pole - 70.45')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1993: Found R.R. spike and 3 witnesses (S40°E - Conc. Mon. 46.60', S87°W - 51.00' - anchor pole, and S40°E - 53.07' - dead 8" W. Pine) as per L.C.R.C.'s Liber 1 Page 41 and Liber 1 Page 44 and is accepted as a careful and faithful perpetuation of the position of the original corner.


SURVEY &
REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: Removed existing corner material and set 5/8" iron rod with brass cap in Mon. Box during a Road Improvement Project for Alcona County Road Commission. Reestablished witnesses are:
 Conc. Mon. - S40°E - 46.60'
 Exis. tag in anchor pole - S87°W - 51.00'
 Set tag #31591 in 9" W. Pine - S44°E - 58.03'
 Set tag #31591 in P. Pole - S46°W - 68.00'



Signed by Thomas L. Fabis Date November 24, 1993
 Surveyor's Michigan License No. 31591