

FEB 07 2001

LAND CORNER RECORDATION CERTIFICATE SECTION FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

2000 Alcona County Remonumentation

Table with 3 columns: FOR CORNERS OF--, LOCATED IN--, CORNER CODE NUMBER. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Section, Lot No., and Private Claims.

Alcona County Remonumentation Liber 2 Page 66

Filed for Record in ALCONA COUNTY MICHIGAN DORIS A GAUTHIER On 09-20-2000 At 09:36 am. LAND CORNER 9.00 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above... established, re-established, monumented, re-monumented, recovered or restored as expressed below...

A. Description of original monument and accessories and/or subsequent restoration:

- E-10: 1838: GLO sur. by L. Clason - set post and referenced 1973: sur. by R. Miller - set 1/2" rod and survey cap by single proportionate method 1992: sur. by Hendricks Eng. - fd. 1/2" iron rod 1993: sur. by NE sur. - fd. 1/2" rod 1994: sur. by Porter's Survey - fd. 1/2" iron rod

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-10: found 1/2" rod with no cap no evidence recovered from GLO survey of 1838 previous witnesses from surveys by Hendricks Eng. and Porter's Survey verify the location for the corner. distances and alignment are compatible with surveys of 1973, 1992, 1993 and 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10: placed 1/2" rod with aluminum cap referenced:

- 28" oak - N 82°E - 42.15 ft 4" j. pine - S 55°E - 68.39 ft 18" oak - S 36°W - 94.64 ft 5" aspen - N 68°E - 55.29 ft 6" oak - N 70°W - 34.25 ft 4" oak - S 71°W - 56.55 ft


APPROVED LAND CORNER P A 345 of 1990 ALCONA COUNTY Date 7-6-2000 County Rep. [Signature]

SIGNED BY [Signature] John F. Oliver DATE Aug. 10, 2000 SURVEYOR'S MICHIGAN REGISTRATION NO. 19840

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____ CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____ MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____