

SURVEY & REMONUMENTATION

FEB 07 2001

2000 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Alcona
(County)

Located in: T27N, R8E Corner Code # J-11 ✓

1. Public Land Survey

T R
T R
T R
T R

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

Alcona County Remonumentation

Liber 2 Page 71

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 09-20-2000 At 09:36 am.
LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John F. Oliver, in a field survey on Aug. 10, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- J-11: 1838: GLO sur. by L. Clason - set post and referenced
- 1912: sur. by A. Freer - corner not identified
- 1980: sur. by D. MacNeill - corner not identified
- 1986: sur. by NE sur - corner not identified
- 2000: sur. by NE sur - fd. 1" pipe 4 ft N. of centerline

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY

Date: 7-6-2000
County Rep: J.F.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11: found 1" pipe 4 ft North of centerline - not capped
no evidence recovered from GLO survey of 1838

the corner location was accepted because of previous surveys of 1980, 1986 and 2000 which distances and alignment were compatible

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11: placed pavement box with 1/2" rod and brass cap referenced:

- power pole - S 52°E - 95.61 ft
- 15" dbl. cedar - N 35°W - 43.80 ft
- 7" cedar - N 35°E - 34.31 ft
- 9" cedar - S 30°W - 81.82 ft



Signed by _____
Surveyor's Michigan License No. 19840

Date Aug. 10, 2000