

001 PAGE 20
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alcona</u> <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>27</u> N R <u>8E</u>	<u>M-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

Remon 1 Page 20

Dec 20 1 19 PM '93

David B. Guthrie
 REGISTER OF DEEDS
 ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

David B. Guthrie in a field survey on August 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- 1838: G.L.O. Survey by Lewis Clason - Set post and referenced Hem. 10 - S48°W 17 / Hem. 9 - N80°W - 27
 1909: Survey by A.J. Freer Jr. - Set stone in center of road
 1977: Survey by David B. Guthrie - Found 1/2" Iron Rod and referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1993: Found nail in the intersection of the center of F-41 and fenceline West. This corner has been accepted for local surveys.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: Set 1/2" X 24" Iron Rod with 3" brass cap stamped to identify the corner referenced:
 N85°W - Fence Corner Post - 47.38 Feet
 N76°W - 4" Spruce - 70.70 Feet
 N83°E - 6" Red Pine - 65.00 Feet
 S18°E - Utility Pole - 182.61 Feet



Signed by *David B. Guthrie* Date 12-20-93
 Surveyor's Michigan License No. 22435