

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Alcona (County), Located In, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

RECORDED

Remon 1 Page 21
DEC 20 1 19 PM '93

David A. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Cell (10, 25) contains a black dot.

I, David B. Guthrie on a field survey on August 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- 1838: G.L.O. Survey by Lewis Clason - Set post and referenced Elm - S64°W - 20 / Beech 6 - N57°W - 40
1904: Survey by A.J. Freer Jr. - Set gray boulder with crockery underneath.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1993: Found nail at the intersection of the center of F-41, French Road East and fenceline West. This corner is a reference for local surveys.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: Set 1/2" X 24" Iron Rod with 3" brass Cap stamped to identify Referenced:
N41°W - Utility Pole - 54.75 Feet
N85°W - 36" Maple - 85.00 Feet
S35°E - 4" Ash - 103.70 Feet
N74°E - Utility Pole - 131.53 Feet



Signed by [Signature]

Date 12-20

Surveyor's Michigan License No. 22435