

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>27N</u> R <u>8E</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED
Remon 1 Page 22

DEC 20 1 19 PM '93

David A. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Guthrie in a field survey on August 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


1838: G.L.O. Survey by Lewis Clason - Set post and referenced
Hem. 14 - S60°W - 74 / Y. Pine 24 - N29°W - 21

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Found iron spike in the center of Highway F-41

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993: Set 1/2" X 24" Iron Rod with 3" brass cap stamped to identify the corner referenced:
S30°W - Utility Pole - 84.36 Feet
S85°E - 15" Jack Pine - 38.88 Feet
N35°E - 12" W. Birch - 51.26 Feet
N42°W - 15" Locust - 42.05 Feet



Signed by *David B. Guthrie* Date 12-20
Surveyor's Michigan License No. 22435