

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

<u>Alcona</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>27NR 8E</u>	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber 1 Page 23

DEC 20 1 19 PM '93

David A. Benthien
REGISTER OF DEEDS
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

David B. Guthrie in a field survey on August 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: G.L.O. Survey by Lewis Clason - Set post and referenced Beech 16 - S39°W - 44 / W. Pine 16 - N59°W - 54
- 1926: Plat of Brownlee Lake Subdivision

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1993: Found spike in the center of Highway F-41

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: Set 1/2" X 24" Iron Rod with 3" brass cap stamped to identify the corner referenced:
 S87°E - Utility Pole - 50.24 Feet
 S50°E - 15" Maple - 37.40 Feet
 West - 30" Aspen - 108.42 Feet
 S41°W - Utility Pole - 68.45 Feet



Signed by *D.B. Guthrie* Date 12-20
 Surveyor's Michigan License No. 22435