

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 N.R. 8 E


Alcona COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 13-14-23-24

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED 10/5/61

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

Power pole - N15W - 46.8 feet

Telephone pole - N52E - 69.6 feet

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division surveyor while making a survey of Section 13. Found large milk can filled with rocks, with rocks on top, buried 28" below surface of road, at centerline intersection of county roads E-W-S. A pine stump in place for Chappel's 1906 NBT, but no sign of his gray boulder or creekery. Considered best available evidence of proper location for corner.

SURVEYOR'S SEAL

SIGNED

Kenneth Ostling
REGISTERED LAND SURVEYOR

DATE 10/9/61