

SURVEY & REMONUMENTATION

FEB 19 1999

SECTION

1998 Alcona County Remonumentation Corner LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1990

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 12-11-1998 At 03:30:10 pm.
LAND CORNER 9.00

For corners in

Alcona	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>27N</u> R <u>9E</u>	<u>C-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Alcona County Remonumentation Page 307

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Date: 4/22/98
County Rep [Signature]

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on April 8, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2			
3												
4	7		8		9		10		11			12
5												
6	18		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: GLO Survey by Thos. Pattison - Set corner post, referenced: Hemlock 15-N60W-50/Beech 13-S37E-50
- 1908: County Survey by A.J. Freer - Ran to corner, referenced: White pine stump 26"-S67E-83.5 links/White pine stump 34"-S46W-27.5 links
- 1996: Field notes by Hank Grush - Found railroad spike.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1998: Remon Survey by Daniel Kibbe - Found railroad spike in C.L. Roads to N-S and East on fence line to West.
- This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1998: Placed 3" Alcona County cap stamped to identify the corner over 1/2" iron rod in monument box.
- Referenced:
- Set tag in fence post-West-27.90'
 - Set tag in P.Pole-N52W-33.1'
 - Set tage in apple-N83E-166.48'
 - Set tag in P. Pole-S45E-72.14'



Signed by [Signature]
Surveyor's Michigan License No. 37278

Date December 7, 1998