

SURVEY & REMONUMENTATION

FEB 19 1999

1998 Alcona County Remonumentation Corner LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County Remonumentation

Liber 1 Page 309

SECTION

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>9E</u>	<u>E-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 12-11-1998 At 03:30:18 pm.
LAND CORNER 9.00
OR

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Date 9/20/98
County Rep D. T. Kibbe

Registrar of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on April 8, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: GLO Survey by Thos. Pattison - Set corner post, referenced: Beech 10-S77E-44/Beech 5-N52W-22
- 1907: County Survey by A.J. Freer - Iron bar and old crockery
- 1996: Field notes by Hank Grush - Found nail over strong tone.
- 1997: Survey by John F. Oliver - Found large PK nail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1998: Remon Survey by Daniel T. Kibbe - Found spike (pulled spike-nothing detected beneath) 1.5' West of N-S C.L. and 5' South of E-W C.L. Also found 3"x 1/2" vertical iron bar which tapered down in size as depth increased. Top of bar was 2.2' below road surface. Wood remnants were found beside iron bar. Corner is 1' East of N-S C.L. and 1' South of E-W C.L. This found iron bar is 4.0' North and 2.4' East of found spike. Raise iron bar to surface with rebar.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1998: Placed 3" Alcona County cap stamped to identify the corner over 1/2" iron rod in monument box.
Referenced:
Top center of telephone box-S53°W-46.09'
N. edge of stop sign post-S83°W-56.14'
Set tag in fence post-N31°E-70.35'
Set tag in fence post-S49°E-51.98'
Found spike-S30°W-4.66'



Signed by Daniel T. Kibbe
Surveyor's Michigan License No. 37278

Date December 7, 1998