

SURVEY & REMONUMENTATION

FEB 19 1999



SECTION

**1998 Alcona County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Alcona County
Remonumentation

For corners in

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 12-11-1998 At 03:31:30 pm.
LAND CORNER 9.00
CR

Alcona (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>9E</u>	<u>G-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Date 9/22/98
County Rep D. T. Kibbe
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16	●	15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

I, Daniel T. Kibbe, in a field survey on April 8, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840: GLO Survey by Thos. Pattison - Set 1/4 section post, Referenced: Hemlock 12-N22W-10/Cedar 6-S2E-30
1997: Survey by John F. Oliver - Found 1/2" bar & cap

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998: Remon Survey by Daniel T. Kibbe - Found bar & cap C.L. road N & S. Fence to W. 1' S of fence to E

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998: Placed 3" Alcona County cap stamped to identify the corner over 1/2" iron rod in monument box.
Referenced:

- Found tag in post-N88E-34.10'
- Found tag in dead maple stump-N70E-42.61'
- Set tag in fence post-S34W-67.09'
- Set tag in fence post-N24W-68.02'
- Found tag in 6" Cedar in cluster-S43E-49.99'



Signed by [Signature]
Surveyor's Michigan License No. 37278

Date December 7, 1998