

1993 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Alcona
(County)

Located in: Corner Code ##

- 1. Public Land Survey T 27N R 9E K - 1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

RECORDED

Remon Liber 1 Page 32

Dec 21 4 21 PM '93

Dennis A. Gauthier
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on August 4, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column K and row 13.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 - Position determined by U.S. Deputy Surveyor. Notes do not indicate that corner was set. However, the line was not run random then true, so the intent was for this to be a corner position. (closing corner)

No monument for this corner was found. However, the standard corner, a concrete monument, does exist and the closing corner may be set using the standard corner and the G.L.O. notes.

No evidence of any monument ever having been set at this location from previous survey work by surveyor's in area.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set a 1/2" re-rod on line between standard corner K-13, T28N, R9E, and L-13, T28N, R9E and at a distance of 6.60 feet East of said standard corner according to original G.L.O. notes.

SURVEY &
REMONUMENTATION

APR 21 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Alcona County Remonumentation Aluminum Cap, appropriately stamped, secured to the set 1/2" re-rod.

Witnesses:

- N 85° W 4.74 12" Cedar
N 75° W 24.28 12" Cedar
S 45° E 41.45 12" Cedar
S 55° W 32.21 10" Cedar

Witnesses were set using duplex nails bearing a brass washer stamped license #19237.

Signed by [Signature] Date December 16, 1993
Surveyor's Michigan License No. 19237

