

1993 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

RECORDED

Alcona (County) Located In: Corner Code #
1. Public Land Survey T 27N R 9E K - 2
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Remon Liber 1 Page 33

Dec 21 4 21 PM '93

Signature of Dennis A. Smith, REGISTER OF DEEDS, ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on August 3, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 - Set by U.S. Deputy Surveyor.

Witnesses:

Cedar 10 N14E 12
Hemlock 6 S32W 14

Found no evidence of above.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Iron Rod with cap #31591 as set and recorded by Thomas L. Fabis, P.S. #31591. After a thorough search revealed no evidence of original monuments or accessories or other pertinent evidence: corner was reset by single proportionate method.

Witnesses:

N 40° W 21.61' 5" Maple
N 25° E 4.27' 15" Twin Maple
S 60° W 8.63' 20" Twin Maple
S 20° E 18.41' 3" Ash

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" iron rod as found was capped with appropriately stamped 1993 Alcona County Remonumentation Aluminum cap and secured to found re-rod.

Witnesses:

N 36° W 21.63' 6" Red Maple Fd.
N 28° E 4.26' 18" Twin Silver Maple Fd.
S 62° W 8.59' 24" Silver Maple Fd.
S 12° E 18.48' 4" Ash Fd.
S 35° E 12.75' 12" Maple D.R.M. Tag.

Witnesses were freshened as necessary; nails replaced with duplex nails bearing a brass washer stamped license #19237

SURVEY & REMONUMENTATION

APR 21 1994

COMMISSION

Signed by Duane R. MacNeill Date December 16, 1993

Surveyor's Michigan License No. 19237

