

APR 21 1994

001 PAGE 34

1993 ALCONA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

Remon Liber 1 Page 34

DEC 21 4 21 PM '93

Doris A. Smithies REGISTER OF DEEDS ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

Form with fields for Alcona (County), Located In: T 27N R 9E, Corner Code: K - 4, and numbered sections 1-5 for survey details.

Grid table with columns A-K and rows 1-13, containing numbers 1-36 and a dot in cell 4-12.

I, Duane R. MacNeill, in a field survey on August 2, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 - Set by U.S. Deputy Surveyor as even split of 80.00 chains.

1975 - Found 3"x3" Cedar Stake by D.R. MacNeill in recorded survey.

1988 - Unrecorded survey R.S. Scott Inc. & Assoc. found 1 1/2 iron bar.

Witnesses:

Fir 8 N18W 16 Cedar 16 S45E 20

No Witnesses

Witnesses:

N 65° W 6.9 8" Aspen N 45° E 4.2 8" Aspen S 40° E 9.3 6" Cedar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 2"x2" iron stake with cap #31591, very beat-up (mushroomed) with witnesses and brush lines during remonumentation field work.

1990 - Corner recorded by T. Fabis P.S. #31591 found existing 2"x2" iron stake with 3 existing witnesses - tagged L.S. #22435.

Witnesses:

N 40° E 4.22' 8" Aspen fd. S 10° E 9.32' 6" Cedar fd. N 80° W 6.92' 7" Aspen fd. S 20° W 15.55' 4" Cedar set.

What was listed by R.S. Scott as 1 1/2" iron bar in 1988 and then by T. Fabis in 1990 as a 2"x2" iron stake must be same iron as witness collaborate same.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Alcona County Remonumentation Aluminum Cap, appropriately stamped, secured to 1/2" re-rod driven next to 2"x2" iron stake.

Witnesses:

N 40° W 20.91 5" Cedar S 40° W 15.40 4" Cedar S 35° E 9.24 5" Cedar N 55° E 4.29 9" Poplar

Signed by [Signature] Date December 16, 1993 Surveyor's Michigan License No. 19237

