

APR 21 1994

1993 ALCONA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 9E

K - 5

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

RECORDED

Remon Liber 1 Page 35

DEC 21 4 22 PM '93

Deane A. MacNeill REGISTER OF DEEDS ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on August 10, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 - Post set by Deputy Surveyor

Unrecorded survey by R.S. Scott Assoc., Inc. in 1988 found 4" square cedar stake and 3/4" iron pipe.

Witnesses:

Hem 26 N11E 36 do 28 S31W 20

Witnesses:

N 85° E 12.0' 24" Hemlock N 85° W 24.6' 18" Maple S 20° E 15.8' 12" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or accessories found.

1993 - Found 3/4" pipe set in 6" crockery as located by field remonumentation crew.

Witnesses, flagging and brush lines indicate frequent use of this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Alcona County Remonumentation Aluminum Cap, appropriately stamped, secured to 1/2" re-rod driven into 3/4" pipe.

Witnesses:

N 05° E 4.01 8" Hemlock N 80° W 24.54 13" Maple S 60° W 14.37 7" Cedar N 80° E 12.01 17" Hemlock S 15° E 15.92 9" Maple

Witnesses were freshened as necessary; nails replaced with duplex nails bearing a brass washer stamped license #19237.

Signed by

Deane R. MacNeill

Date December 16, 1993

Surveyor's Michigan License No. 19237

Grid table with columns A-L and rows 2-13. A dot is present at row 5, column J.

