

SURVEY & REMONUMENTATION

APR 21 1994

COMMISSION

001 PAGE 36

1993 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|----------------------------|--------------|
| 1. Public Land Survey | T <u>27</u> N R <u>9</u> E | <u>K - 6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECORDED

Remon Liber 1 Page 36

Dec 21 4 25 PM '93

Janice A. Bentler
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Duane R. MacNeill, in a field survey on August 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 - Set by U.S. Deputy Surveyor as even split of 80.00 chains.

1980 - D.R. MacNeill P.S. #19237 found and used concrete monument with 3/4" pip inside.

Witnesses:

Maple 15 S27W 33
Beech 9 N27N 42

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Remonumentation field crew found concrete monument with 3/4" pipe inside. Evidence (flagging, etc.) indicates use of this corner by other surveyors.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Alcona County Remonumentation Aluminum Cap, appropriately stamped, secured to 1/2" re-rod driven into 3/4" pipe in concrete monument.

Witnesses:

N 85° W 34.66 15" Oak
S 10° W 22.28 13" Maple
N 05° E 21.36 20" Beech
S 75° E 20.03 5" Maple

Witnesses were duplex nails bearing a brass washer stamped license #19237

Signed by *Duane R. MacNeill* Date December 16, 1993
Surveyor's Michigan License No. 19237

