

**SURVEY & REMONUMENTATION**

APR 21 1994

1993 ALCONA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27</u> N R <u>9</u> E	<u>K - 7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

Remon Liber 1 Page 43  
DEC 21 4 25 PM '93

*David A. Guthrie*  
REGISTER OF DEEDS  
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on August 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
**1838 - Set by Lewis Clason, U.S. Deputy Surveyor.**

Witnesses:

Maple 6 S25W 8  
W. Birch 9 S62E 52

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
**1991 - Corner used in M.D.O.T. survey by Cliff Lindgren P.S. #14098 - Stone with chiseled "x"**

Witnesses:

South 11.65' 16" Oak  
West 24.45' 16" Pine  
S15°W 19.00' 22" Pine  
S86°E 15.10' 18" Pine

1993 - Remonumentation crew found stone with chiseled "x" on top and set 1/2" re-rod in exact location and moved stone to side.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Alcona County Remonumentation Aluminum Cap, appropriately stamped, was secured to 1/2" re-rod as described above.**

Witnesses:

South 11.64 16" Oak  
West 24.45 16" Pine  
S15°W 19.02 22" W. Pine  
S86°E 15.11 18" N. Pine  
S55°W 9.43 6" Maple

Witnesses were freshened as necessary; nails replaced with duplex nails bearing a brass washer stamped license

Signed by *Duane R. MacNeill* Date December 16, 1993  
Surveyor's Michigan License No. 19237

