

APR 21 1994

1993 ALCONA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona

(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 27N R 9E      K - 8  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling      S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**RECORDED**  
 Remon Liber 1 Page 42  
**DEC 21 4 22 PM '93**  
*Denis A. Swartz*  
 REGISTER OF DEEDS  
 ALCONA COUNTY, MICHIGAN  
**Register of Deeds Stamp & File Number**

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

I, Duane R. MacNeill, in a field survey on August 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
1838 - Set by U.S. Deputy Surveyor as even split of 80.00 chains.

Witnesses:

- Y. Pine 18 N49E 28
- Beech 8 S30W 16

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
**No evidence of original monument or accessories found after a thorough search.**  
1993 - Remonumentation crew found 1" square steel pin driven in the root of a large oak as used in a M.D.O.T. survey in 1991 by Cliff Lindgren, P.S. #14098. Set 1/2" re-rod adjacent to 1" square steel pin on West side.

Witnesses:

- West 24.36 8" Maple
- N 25° W 32.55 25" Tri-Maple
- N 15° E 42.50 26" Tw. Maple
- S 05° E 28.24 12" Birch

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**Alcona County Remonumentation Aluminum Cap, appropriately stamped, secured to 1/2" re-rod.**

Witnesses:

- Due West 24.23 8" Maple
- N 25° W 32.59 25" Tri-Maple
- N 15° E 42.69 26" Twin Maple
- S 05° E 28.26 12" Birch

Witnesses were freshened as necessary; nails replaced with duplex nails bearing a brass washer stamped license #19237.

Signed by *Duane R. MacNeill*  
 Surveyor's Michigan License No. 19237

Date December 16, 1993

