

APR 21 1994

1993 ALCONA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona

(County)

Located in:

Corner Code #

1. Public Land Survey

T 27N R 9E

K - 9

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

RECORDED

Remon Liber 1 Page 44

DEC 21 4 23 PM '93

*David A. Buntchies*  
REGISTER OF DEEDS  
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on August 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1838 - Set by U.S. Deputy Surveyor

1970 - Recorded survey by James G. Campbell  
P.S. #15397 references "stone" as K-9.

Witnesses:

Hem 15 N26E 37  
Beech 6 S23W 21

No Witnesses recorded.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1979 - Recorded survey by Duane R. MacNeill  
P.S. #19237 references 9"x6" stone as K-9.

1993 - Remonumentation survey crew found light colored pointed stone and set 1/2" re-rod in exact location and set stone to side.

Witnesses:

S 21° E 15.52' 9" Poplar  
N 57° W 21.30' 8" Birch  
N 03° W 43.52' 8" Maple

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Alcona County Remonumentation Aluminum Cap, secured to 1/2" Re-rod as described above, appropriately stamped.

Witnesses:

N 21° E 15.55 10" Poplar  
N 57° W 21.28 9" Birch  
N 03° W 43.50 9" Maple  
N 45° E 9.75 4" Maple

Witnesses were freshened as necessary; nails replaced with duplex nails bearing a brass washer stamped license #19237.

Signed by

*Duane R. MacNeill*

Date December 16, 1993

Surveyor's Michigan License No. 19237

