

FEB 17 1994

001 PAGE 59

COMMISSION

1993 ALCONA COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County
Remonumentation
Liber 1 Page 59

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>9E</u>	<u>L - 7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

DEC 30 1 27 PM '93

Doris A. Gauthier
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Duane R. MacNeill, in a field survey on December 14, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840 - Set by U.S. Deputy Surveyor at 40 chains East of NW Section corner on Shore of Lake Huron.

1978 - John Oliver, R.L.S. found 1/2" re-rod.

1981 - Nicholas B. DeYoung, R.L.S. found 1/2" re-rod.

Witnesses:

TAM 6 S62W 50
No others

No Witnesses

Witnesses:

N 50° W 14.2 8" Oak
S 85° W 27.8 12" Cedar
S 70° E 30.6 12" Cedar
S 45° W 47.8 NW corner of house.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Remonumentation Crew found only one remaining witness and no survey pin at corner location. Corner was restored by using survey pins as set by Nicholas B. DeYoung, R.L.S. to the West of said North 1/4 corner of Section 24 and a 1/2" re-rod (30" long) was driven at that location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Alcona County Remonumentation Aluminum Cap, appropriately stamped, secured to 1/2" re-rod.

Witnesses:

N 05° W 17.27 5" Spruce
S 75° W 44.92 Quad 10" Maples
S 60° W 30.99 8" Cedar
S 45° E 31.02 14" Cedar
S 45° W 47.9 NW corner of house.

Witnesses were duplex nails bearing a plastic cap stamped License #19237.

Signed by

Duane R. MacNeill

Date December 29, 1993

Surveyor's Michigan License No. 19237