

**SURVEY & REMONUMENTATION**

FEB 17 1994

COMMISSION

001 PAGE 57

1993 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County Remonumentation

Liber 1 Page 57

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>9E</u>	<u>L - 9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

DEC 30 1 26 PM '93

*Doris A. Bantline*  
REGISTER OF DEEDS  
ALCONA COUNTY, MICHIGAN  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Duane R. MacNeill, in a field survey on December 14, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840 - Set by U.S. Deputy Surveyor as even split of 80.56 chains.

1978 - Found 3/4" pipe by John Oliver, R.L.S.

1991 - Found stone with chiseled "x" on top by Cliff Lindgren, R

Witnesses:

No Witnesses

Witnesses:

Cedar 8 N81W 42  
Cedar 6 S35E 13

S 43° W 14.32 5" Cedar  
S 65° E 6.06 10" Tw. Ce  
S 07° E 29.43 5" Cedar  
N 85° W 30.89 8" Cedar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Remonumentation Survey Crew found 3/4" pipe by stone with chiseled "x" on top. Crew set 1/2" re-rod in exact location of stone and witnessed same.

No evidence of original corner or accessories found after thorough search.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Alcona County Remonumentation Aluminum Cap, appropriately stamped, secured to 1/2" re-rod.

Witnesses:

S 65° E 6.20 10" Twin Cedar  
N 85° W 30.82 8" Cedar  
S 43° W 14.35 5" Cedar  
S 07° E 29.51 5" Cedar

Witnesses were freshened as necessary; nails replaced with duplex nails bearing a plastic cap license #19237.

Signed by *Duane R. MacNeill* Date December 29, 1993  
Surveyor's Michigan License No. 19237