

1993 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona

(County)

Located in:

Corner Code #

1. Public Land Survey

T 27N R 9-10E

M - 9

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

RECORDED

Remon Liber 1 Page 30

DEC 21 4 21 PM '93

Doris A. Guthrie REGISTER OF DEEDS ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Duane R. MacNeill, in a field survey on August 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 - Corner set by U.S Deputy Surveyor.

Witnesses:

W. Birch 12 S43W 10 Cedar 9 N45W 30

SURVEY & REMONUMENTATION

APR 21 1994

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or accessories found after a thorough search.

Found Michigan D.N.R. monument - 4" steel pipe with 4" brass cap, stamped as to Section, Twp. and Range and surveyor license #5336.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The D.N.R. monument as found was accepted and used in place.

Witnesses:

N 10° E 17.11 4" Cedar S 80° W 25.04 8" Ash S 35° E 19.07 5" Balsam S 45° W 33.53 5" Balsam

Witnesses were duplex nails bearing a brass washer stamped license #19237.

Signed by Duane R. MacNeill Surveyor's Michigan License No. 19237

Date December 16, 1993

