

1993 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 9-10E

M - 10

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

RECORDED

Liber 268 Page 31

Dec 21 4 21 PM '93

David A. Smith

REGISTER OF DEEDS  
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Duane R. MacNeill, in a field survey on December 1, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 - Cedar post set by Lewis Clason, Deputy Surveyor.

1972 - Corner recorded by Donald Marlatt #18660. Found 1 1/2" pipe; believed established in 1934 by George Henni.

Witnesses:

Cedar 6 S63W 38  
do 8 N70W 30

Witnesses:

East 5.4' 6" Tamrack  
N80°W 14.5' 5" Tamrack

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or accessories found after a thorough search.

1993 - Remonumentation survey crew found concrete monument next to 1 1/2" pipe.

1991 - Recorded survey by D.R. MacNeill references this corner as being a 4" concrete monument.

SURVEY & REMONUMENTATION

APR 21 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Alcona County Remonumentation Aluminum Cap, appropriately stamped, secured to re-rod extending from concrete monument.

Witnesses:

N 15° W 21.65 5" Cedar  
N 40° E 14.89 6" Cedar  
S 85° E 7.23 8" Cedar  
S 10° W 10.73 6" Cedar

Witnesses were duplex nails bearing a brass washer stamped license #19237

Signed by Duane R. MacNeill

Date December 16, 1993

Surveyor's Michigan License No. 19237

