

SURVEY & REMONUMENTATION

APR 21 1994

001 PAGE 48
1993 ALCONA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>9-10E</u>	<u>M - 11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

Remon Liber 1 Page 48

DEC 21 4 23 PM '93

Doris A. Benthien
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on December 1, 19 93,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1838 - Set by Lewis Clason, U.S. Deputy Surveyor - Cedar post.

1972 - Recorded by Donald Marlatt #18660 Found 1 1/2" pipe and 3"x3" Sq. Cedar stake believed established in 1934 by George Henning.

Witnesses:

Cedar 7 S42 1/2 W 22
do 6 N12 1/2 W 05

Witnesses:

N 65° W 9.05' Pine stump
N 45° W 23.5' 10" Cedar

N.B.T.'s - not dated

W. Pine stump 24 N22E 69
do 30 S65 1/2 W 85

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or accessories found after a thorough search.

1993 - Remonumentation crew found 1 1/2" pipe and 6" square monument with no re-rod or iron in same. The crew drove a 1/2" re-rod into the 1 1/2" pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Alcona County Remonumentation Aluminum Cap, secured to 1/2" re-rod driven into 1 1/2" pipe, appropriately stamped.

Witnesses:

N 50° E 11.23 10" Cedar
N 30° W 28.08 12" Cedar
S 45° W 10.16 8" Cedar
S 45° E 6.21 6" Cedar

Witnesses were duplex nails bearing a brass washer stamped license #19237.

Signed by

Duane R. MacNeill

Date December 16, 1993

Surveyor's Michigan License No. 19237

