

SURVEY & REMONUMENTATION

APR 21 1994

1993 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Alcona (County) Located In: Corner Code #

1. Public Land Survey	T <u>27N</u> R <u>9-10E</u>	<u>M - 12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED
 Remon Liber 1 Page 47
 DEC 21 4 23 PM '93
Doris A. Guthrie
 REGISTER OF DEEDS
 ALCONA COUNTY, MICHIGAN
 Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on August 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 - Cedar post by U.S. Deputy Surveyor

Witnesses:

Cedar 14 S44W 30
 do 12 N7½W 40

N.B.T.'s - no date

W. Pine stump 24 N22E 69
 Do 30 S65½W 85

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In 1974 a 3"x3" cedar stake found at this location by D.R. MacNeill, P.S. 19237. No evidence of original corners or accessories; no evidence of N.B.T.'s. A 1" capped pipe was set next to cedar stake.

Witnesses:

N 40° E 67.05' 6" Spruce
 S 55° E 9.06 6" Cedar

Corner re-witnessed in 1976 by D.R. MacNeill

S75°E 9.18 6" Cedar (matches left)
 N25°E 12.46' 5" Balsam
 N80°W 18.63' 12" Cedar

1993 - Remonumentation crew found 1" pipe and "T" bar on West side of pipe. Crew drove 1/2" re-rod into 1" pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Alcona County Remonumentation Aluminum Cap, secured to 1/2" re-rod driven into 1" pipe, appropriately stamped.

Witnesses:

N 05° E 26.59 6" Cedar
 S 80° E 8.99 6" Cedar
 Due South 12.74 8" Cedar
 Due West 18.55 12" Cedar

Witnesses were freshened as necessary; nails replaced with duplex nails bearing a brass washer stamped license #19237

Signed by Duane R. MacNeill
 Surveyor's Michigan License No. 19237

Date December 16, 1993

