

**SURVEY &
REMONUMENTATION**

001 PAGE 46

APR 21 1994

1993 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Alcona

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|--------------|---------------|
| 1. Public Land Survey | T | <u>27N</u> | R | <u>9-10E</u> | <u>M - 13</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

RECORDED

Remon Liber 1 Page 46

DEC 21 4 23 PM '93

Doris A. Gauthier
REGISTER OF DEEDS
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Duane R. MacNeill, in a field survey on August 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 - Post set by Lewis Clason - U.S. Deputy Surveyor.

N.B.T.'s penciled into original notes by County Surveyor - not dated.

Witnesses:

Cedar 8 N58W 18
Fir 8 N22E 03

Cedar stump 14 N51½W 17
W. Pine stump 20 S24½E 29

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - No existing evidence of original monuments or accessories after thorough search. No existing evidence of N.B.T.'s after thorough search. Found 1" pipe in centerline of Trask Lake Rd. & drove ½" re-rod into pipe. Pipe has been used and witnessed as M-13 on recorded surveys.

1992 - Corner recorded as 1" pipe by Cliff Lindgren P.S. #14098 and used in M.D.O.T. survey.

Witnesses:

North 31.18' Fence Post
S15°W 43.95' 14" Maple
S45°E 30.80' Power Pole

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Alcona County Remonumentation Aluminum Cap, secured to 1/2" re-rod driven into pipe, appropriately stamped.

Witnesses:

S 15° W 43.95' 14" Maple
S 45° E 30.80' P. Pole
N 45° E 37.94' G. Pole
N 19° E 32.97' Concrete Monument

Witnesses were freshened as necessary; nails replaced with duplex nails bearing a brass washer stamped license #19237.

Signed by Duane R. MacNeill
Surveyor's Michigan License No. 19237

Date December 16, 1993

