

**SURVEY & REMONUMENTATION**

RECORDED

APR 25 1995

1994 Alcona County Remonumentation Corner

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

Nov 7 2 08 PM '94

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>5E</u>	<u>D-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*David A. Guthrie*  
REGISTER OF DEEDS  
ALCONA COUNTY, MICHIGAN

Alcona County  
Remonumentation  
Liber 1 Page 62  
E.T.L.  
Register of Deeds Stamp & File Number

I, David B. Guthrie in a field survey on May 17, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	16	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

- A. Description of original monument and accessories and/or subsequent restoration:
- 1840: G.L.O. Survey by Thos. Pattison - Set post and referenced W. Pine 28 - S32E - 11 / W. Pine 26 - N22W - 8
  - 1910: Survey by W.S. Freer - Found Original Corner
  - 1993: Survey by Norman Quaine - Found 1/2" Iron Rod

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1994: Found 1/2" Iron Rod

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1994: Replaced with 5/8" Iron Rod with 3" Brass Cap stamped to identify the corner placed in a Monument Box.
- Referenced -
- N30°W - Utility Pole - 44.14 feet
  - N30°E - Concrete Project Marker - 33.50 feet
  - S49°W - Ely. Gate Post - 44.90 feet
  - S40°W - Utility Pole - 60.36 feet



Signed by *David B. Guthrie* Date Nov. 5, 1994

Surveyor's Michigan License No. 22435