

**SURVEY &
REMONUMENTATION**

APR 24 1995

COMMISSION

1994 Alcona County Remonumentation Corner

Alcona County
Remonumentation
Liber 1 Page 90

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #	Liber
1. Public Land Survey	T <u>28N</u> R <u>5E</u>	<u>F-11</u>	<u>Dec 19 12 15 PM 1994</u>
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

APPROVED LAND CORNER
P.A. 345 of 1990
ALCONA COUNTY
Date 12-19-94
County Rep. E. J. L.

RECORDED

REGISTER OF DEEDS
ALCONA COUNTY MICHIGAN
David A. Guthrie
E. J. L.
Register of Deeds Stamp & File Number

I, David B. Guthrie in a field survey on June 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	13	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1840: G.L.O. Survey by Thos. Pattison - Used 16" Hemlock for Corner
No references.
 - 1910: Survey by W.S. Freer - Set 5"x5" W.Pine stake - Referenced
W.Pine stake - S22°W - 95 Links
 - ±1970: Survey by Norman C. Caldwell - Set nail with cap

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1994: Found nail with cap No. 12018 3 feet North of the centerline of McCollum Lake Road.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1994: Replaced with a 5/8" Iron Rod with a 3" Brass Cap stamped to identify the Corner placed in a Monument Box.
Referenced -
 - S68°W - Utility Pole - 53.13 Feet
 - S28°E - 15" Maple - 87.00 Feet
 - N65°E - 10" W.Pine - 84.01 Feet
 - N55°W - 5" Oak - 68.61 Feet



Signed by *D.B. Guthrie* Date Dec 16, 1994
Surveyor's Michigan License No. 22435