

SURVEY & REMONUMENTATION

MAR 09 2000

1999 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County
 Remonumentation
 Liber 2 Page 1

SECTION
 For corners in

Alcona (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28</u> N R <u>5E</u>	G-1
	T <u> </u> R <u> </u>	<u>Mitchell Twp.</u>
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____

0
 Filed for Record in
 ALCONA COUNTY MICHIGAN
 DORIS A GAUTHIER
 On 12-17-1999 At 10:07 am.
 LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Thomas L. Fabis, in a field survey on Oct. 28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: G.L.O. Survey Thomas Pattison Inters. N.B. 42 links E. of Post, set post & referenced.
- 1913: County Survey W.S. Freer Norway Stake 4x4 3 foot high.
- 1932: Alpena County Survey W.H. LeRoy dug up old cor. & replaced with auto drive shaft housing in North wheel track.
- 1983: Survey Liber 246 Page 109 Ray Kostecke referenced corner.
- 1984 & 1987: R.S. Scott Surveys David Guthrie set 1/2" iron rod by extension of previous survey & referenced.
- 1997 & 1998: NELS Surveys Bill Woods measures to corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999: Found auto drive shaft housing 4 feet below gravel road surface, 7 foot North of centerline of Doctor's Club Rd. Also, found existing pipe S49E 11.58 feet and 1/2" iron P.S. #22435 S 20° 30' E 22.59 feet from this corner.


The auto drive shaft housing is believed to be the same corner set and used by W.H. LeRoy in 1932 and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1999: Set 1/2" iron rod with a 3" dia. alum. cap, stamped to identify the corner inside a 1" iron pipe 5 feet long over the location of the existing auto drive shaft housing. Witnesses are:
 10" Aspen N14E 28.77
 24" Oak S10E 35.17
 14" Oak S10W 42.86
 30" Oak N54W 52.84

APPROVED LAND CORNER
 P A 345 of 1990
 ALCONA COUNTY
 Date: 11/30/99
 County Rep: D.A.B.E.

Signed by Thomas L. Fabis
 Surveyor's Michigan License No. 31591



Date December 1, 1999