

MAR 03 2000

1999 ALCONA COUNTY REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alcona</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>28</u> NR <u>5E</u>	G-4
	T ___ R ___	<u>Mitchell</u> Twp.
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Alcona County
Remonumentation
Liber 2 Page 10

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 12-17-1999 At 10:07 am.
LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas L. Fabis, in a field survey on Aug. 30, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: G.L.O. Survey Thomas Pattison set post & referenced: W. Pine 18 N48E 5, W. Pine 16 S50W 5.
- 1916: County Survey W.S. Freer W. Oak stake 3x3 4 foot long.
- 1959: M.D.O.T. Witness Card Norm Caldwell found 2" axle shaft & referenced.
- 1960: M.D.O.T. Road Plans 2" Axle shaft same 3/4" Iron Rod & referenced.
- 1996: NELS Survey Bill Woods found 5/8" Bar, D.O.T.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999: Found 3/4" iron 19.5 feet East of M-65 centerline. Also found one witness 15" Oak S86E 112.54 as per M.D.O.T. Witness Card and Road Plans by Norm Caldwell.

The position of this corner is compatible with local and M.D.O.T. surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1999: Removed 3/4" iron and replaced with 1/2" iron rod with a 3" dia. alum. cap, stamped to identify the corner. Set tag #31591 in the following witnesses:
9" Oak N38E 84.70
7" R. Pine S84E 57.48
6" J. Pine S54W 86.96
6" Oak in Clump S38E 83.14

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY

Date: 9/23/99
County Rep. [Signature]

Signed by Thomas L. Fabis
Surveyor's Michigan License No. 31591



Date November 30, 1999