

MAR 08 2000

SECTION

1999 Alcona County Remonumentation Corner LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>5E</u>	<u>G-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Alcona County Remonumentation Liber 2 Page 35

Filed for Record in ALCONA COUNTY MICHIGAN DORIS A GAUTHIER On 12-17-1999 At 10:55 am. LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Daniel T. Kibbe, in a field survey on June 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: GLO Survey by Thos. Pattison-Set corner post. Referenced: B. Oak 10-S68E-33/W. Oak 4-N36W-45
- 1913: W.S. Freer Survey for Commissioner of Highways-Visited Corner
- 1916: W. S. Freer-Visited Corner
- 1927: County Survey by W.S. Freer-Cedar stake 4"x4" by 4' long; sleigh shoe cast 2' long by 2"x2.5". Referenced: W. Pine Stump 20-S35.5E-150
- 1955: MDOT Plans by Norman Caldwell-Found 3/4" Iron rod. Fences east and west. Referenced: 12" Oak-S35W-163.12'/20" Oak-S65W-112.23'/14" Oak-N80W-84.82'
- 1955: Recorded Corner by Norman Caldwell-Found 1.5"x2" iron bar. Referenced: 12" Oak-S35W-163.12'/20" Oak-S65W-112.23'/14" Oak-N80W-84.82'
- 1959: MDOT Survey by Norman Caldwell-Found 1.5" x 2" Iron Bar. Corner is PI STA 1227+68.45. Referenced: 12" Oak-S35W-163.12'/20" Oak-S65W-112.23'/14" Oak-N80W-84.82'
- 1990: Survey by Earl T. Lewis-Existing mon. box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999: Remon. Survey by Daniel T. Kibbe-Found 3/4" bar in mon. box in CL M-65 on fence Line East.
This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999: Placed 3" Alcona County cap stamped to identify the corner over 3/4" iron rod in monument box.
Referenced:
8" Red Pine-set tag-N52 E 77.90'
Con. R/W marker-Chisled X in top-S88 E 75.22'
Con. R/W marker-Chisled X in top-S74 W 74.96'
9" Red Pine-set tag-N89 W 102.98'

APPROVED LAND CORNER P A 345 of 1990 ALCONA COUNTY Date: 9/27/99 County Rep. [Signature]

Signed by [Signature] Surveyor's Michigan License No. 37278

Date November 30, 1999

