

SURVEY & REMONUMENTATION

1994 ~~APR 25 1985~~ Alcona County Remonumentation Corner

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

Nov 7 2 08 PM '94

For corners in

<u>Alcona</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>5E</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

David A. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Alcona County Remonumentation
Liber 1 Page 64

E.T.L.

Register of Deeds Stamp & File Number

David B. Guthrie in a field survey on May 17, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1840: G.L.O. Survey by Thos. Pattison - Used a 10" Hemlock for the corner. No References.
 - 1910: Survey by W.S. Freer - Set a 4"x4" Oak Stake
 - 1916: Survey by W.S. Freer - Set a 3/4"x18" Iron Stake
 - 1959: Survey by M.D.S.H. - Found a 1/2" Iron Pin

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1994: Found 3/4" Iron Rod in Monument Box at the road intersection.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1994: Replaced with 5/8" Iron Rod with a 3" Brass Cap stamped to identify the corner placed in a Monument Box.
Referenced -
N64°E - 15" Basswood - 173.30 feet
N57°W - 12" Birch - 183.45 feet
N48°W - 12" Oak - 174.70 feet
S45°W - 16" Oak - 229.22 feet



Signed by David B. Guthrie Date Nov. 5, 1994
Surveyor's Michigan License No. 22435