

MAR 0 8 2000

1999 Alcona County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Alcona (County)	Located In:	Corner Code #
1. Public Land Survey	T 28N R5E	G-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Alcona County
Remonumentation
Sheet 2 Page 36

U
0
Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 12-17-1999 At 10:55 am.
LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel T. Kibbe, in a field survey on June 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: GLO Survey by Thos. Pattison-Set corner post. Referenced: Spruce Pine 12-N48E-90/ Spruce Pine 5-N45W-140
- 1927: County Survey by W. S. Freer-Original corner. Bolt 3/4" by 18" long. Referenced: Iron Bolt 7/8"x 18" N48E-90 links.
- 1955: MDOT Plans by Norman Caldwell-3/4" pin in 1.25" pipe 474.80' left of Station 1121+85.06 on survey tangent. Referenced: 11" Oak-S24W-33.79'/ 9" Oak-N31W-22.92'/ 14" Oak-N74E-35.55'
- 1973: Survey by Norman C. Caldwell-Found 3/4" bar in pipe. Referenced: 11" Oak-N37W-22.7'/15" Oak-N73E-35.0'/14" Oak-S24W-33.5'/ N Cor 3 & 4-East-23.1
- 1973: Survey by Norman C. Caldwell-Referenced corner 23.1' West of NW corner of 3

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999: Remon. Survey by Daniel T. Kibbe-Found 3/4" bar in pipe 23.2' West of G-1 T27N R5E.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1999: Placed 3" Alcona County cap stamped to identify the corner over 3/4" iron rod. Referenced:

- 18" Oak-found tag 15410-N35 W 22.70'
- 20" Oak-found MSHD tag-S21 W 33.77'
- 22" Oak-found MSHD tag-N77 E 35.55'
- Bar & Cap #12018 East 23.20'

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Date 9/23/99
County Rep. *Daniel T. Kibbe*

Signed by *Daniel T. Kibbe*
Surveyor's Michigan License No. 37278



Date November 30, 1999