

MAR 03 2000

1999 Alcona County Remonumentation Corner  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

Alcona (County)	Located In:	Corner Code #
1. Public Land Survey	T 28N R5E	1-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Alcona County  
Remonumentation  
Blk 2 Page 30

U Filed for Record in  
ALCONA COUNTY MICHIGAN  
DORIS A GAUTHIER  
On 12-17-1999 At 10:55 am.  
LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Daniel T. Kibbe, in a field survey on June 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: GLO Survey by Thos. Pattison-Set corner post. Referenced: Spruce Pine 4-N31W-20/Spruce Pine 4-S30E-8
- 1916: Survey by W.S. Freer-Visits corner in surveys of Section 10 and 15
- 1927: County survey by W.S. Freer-Cedar stake 4"x4"x3' long with stones around stake. Referenced: 30 Small Stones-S53E-59
- 1986: Survey by John Oliver-Found 1/2" bar
- 1991: Survey by Duane R. MacNeill-Found 1/2" rerod
- 1995: Survey by Mitchell & Associates-Found 1/2" rebar @ cl/cl. Referenced: Found nail in 13" Oak-S75E-33.16'/Found nail in 13" Oak-831W-69.08'/Found nail in 11" Oak-N27W-60.50'/Set nail in P. Pole-N45W-44.53'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999: Remon. Survey by Daniel T. Kibbe-Found 1/2" rebar CL of N-S road 1' South of Road to West.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1999: Placed 3" Alcona County cap stamped to identify the corner over 1/2" iron rod. Referenced:  
18" Dead Oak-found spike & blaze-S71E 33.11'  
P. Pole-found spike-N47E 44.47'  
12" Oak-found spike & blaze-N25W 60.43'  
18" Twin Oak-found spike & blaze-S31W 69.01'

APPROVED LAND CORNER  
P A 345 of 1990  
ALCONA COUNTY  
Date: 9/23/99  
County Rep *[Signature]*

Signed by *[Signature]*  
Surveyor's Michigan License No. 37278

Date November 30, 1999

