

MAR 03 2000

1999 Alcona County Remonumentation Corner  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Alcona County  
Remonumentation  
Libr 2 Page 29

Alcona (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>5E</u>	<u>I-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Filed for Record in  
ALCONA COUNTY MICHIGAN  
DORIS A GAUTHIER  
On 12-17-1999 At 10:55 am.  
LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel T. Kibbe, in a field survey on June 2, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: GLO Survey by Thos. Pattison-Set 1/4 post. Referenced: W. Pine 9-S27W-35/W. Pine 6-N43E-50
- 1916: Survey by W.S. Freer-Referenced corner
- 1927: County survey by W.S. Freer-Cedar stake 4"x4"x4' long
- 1991: Survey by Duane R. MacNeill-Referenced corner.
- 1995: Survey by Mitchell & Associates-Set 1/2"x20" rerod at SP of I-5 and I-7, 12' South of two-track and 9' South of old wire fence with no post. Referenced: Set nail in 14" Oak-N40W-74.06/Set nail in 15" Oak-S65W-47.72/Set nail in 8" Jack Pine-S37E-57.42/Set nail in 6" Oak-N34E-68.58'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999: Remon. Survey by Daniel T. Kibbe-Found 7/8"x17" solid iron rod 0.5' deep in CL N-S road 43' South of trail to East and hunt wire to West. /Also found B & C #R.F.M. LLS 28417, LLS 30079 P.D.C. 2' West of CL N-S Road 16' South of CL trail to East and hunt wire to West 2' West CL N-S road.

The 7/8"x17" iron bar is of unknown origin and does not fit any occupation or S.P. position so is therefore disregarded. The B+C is at an S.P. position using the found B+C at corner I-7 which was subsequently not used, therefore, the B+C at I-6 is disregarded. Contractor proposes to set I-6 at S.P. position between I-5 and the accepted corner at I-7. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1999: Placed 3" Alcona County cap stamped to identify the corner over 1/2" iron rod. Referenced:  
9" Jack-pine-set tag S25E 56.81'  
18" Oak-set tag N42W 75.40'  
18" Oak-set tag S70W 54.38'  
10" Oak-set tag N35E 62.55'  
RFM/PDC B+C S57W 6.64'  
7/8"x17" Iron Rod S06W 30.47'

APPROVED LAND CORNER  
P A 345 of 1990  
ALCONA COUNTY  
Date 9/23/99  
County Rep. D.D.B.

Signed by Daniel T. Kibbe  
Surveyor's Michigan License No. 37278

Date November 30, 1999

