

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

Remon 1 Page 10

DEC 20 1 17 PM '93

David B. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

or corners in

Alcona
County

Located In:

Corner Code #

Public Land Survey	T	28N	R	7E	M-4
	T		R		
	T		R		
	T		R		
Property Controlling	S		T		R
in Section	S		T		R
Miscellaneous	S		T		R
Property in Sec.	S		T		R

Lot No. _____, Recorded Plat _____
Private Claims _____

David B. Guthrie in a field survey on September 30, 1993,
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of original monument and accessories and/or subsequent restoration:

1839: G.L.O. Survey by Lewis Clason - Set post and referenced
Elm 12 - S72°W - 10 / Tam. 16 - N54°W - 13

1988: Survey by David B. Guthrie, Set 1/2" Iron Rod

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Found 1/2" Iron Rod set by David B. Guthrie in 1988 by
single proportion between the recovered Northeast and Southeast
corners of Section 12.

SURVEY &
REMONUMENTATION

1993

COMMISSION

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993: Set 1/2" X 24" Iron Rod with 3" aluminum cap stamped to
identify the corner. Referenced

N25°E - 6" Cedar - 19.05 Feet
N85°W - 6" Pine - 23.80 Feet
S30°E - 7" Cedar - 27.20 Feet



Signed by *David B. Guthrie*

Date 12-20

Surveyor's Michigan License No. 22435