

1993 Alcona County Remonumentation Corner

Alcona County Remonumentation Liber 1 Page 12

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Alcona (County), Located in:, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

RECORDED Remon 1 Page 12 DEC 20 1 17 PM '93

Signature of David A. Guthrie, REGISTER OF DEEDS, ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, David B. Guthrie in a field survey on Sept. 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1839: G.L.O. Survey by Lewis Clason - Set post and referenced W. Birch 6 - S8°W - 25 / Aspen 10 - N22°W - 23

1962: Survey by James L. Scott for Plat of Tollson Subdivision

1981: Survey by David B. Guthrie - Found 1" Iron Pipe and Referenced

1993: Survey by David B. Guthrie - Found 1" Iron Pipe, verified previous references.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Found 1" Iron Pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


1993: Set 1/2" X 24" Iron Rod with a 3" brass cap Stamped to identify the corner. Referenced -

N31°E - Utility Pole - 74.18 Feet

N53°E - Twin 6" Ash - 42.00 Feet

S70°E - 6" Aspen - 33.60 Feet

S39°E - 7" Aspen - 83.00 Feet



Signed by [Signature] Date 12-1

Surveyor's Michigan License No. 22435