

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

Remon 1 Page 13

DEC 20 1 18 PM '93

Alcona (County)

Located In:

Corner Code --#

- 1. Public Land Survey T 28N R 7E M-7
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

David A. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Guthrie in a field survey on Sept. 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- 1839: G.L.O. Survey by Lewis Clason - Set post and referenced Hem. 36 - N50°W - 38 / Hem. 6 - S70°W - 40
- 1903: County Survey by Edw. Chappelle Sr. - Found N.B.T.S., set corner
- 1921: Survey by Jos. McNeil for the Plat of East Bay Park.
- 1961: Survey by James L. Scott for the Plat of Bay Side Park.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1993: Found 1/2" Iron Rod 3' West of the Center of Hubbard Lake Road and 33 Feet East of a Concrete Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: Set 1/2" x 24" Iron rod with a 3" brass cap stamped to identify the corner. Referenced -
 N24°W - Utility Pole - 47.67 Feet
 N40°E - Utility Pole - 51.87 Feet
 S78°E - 24" Oak - 50.35 Feet
 S41°E - 5" Aspen - 52.05 Feet
 West - Concrete Monument - 33.00 Feet



Signed by David B. Guthrie Date 12-1
Surveyor's Michigan License No. 22435