

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alcona</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>7E</u>	<u>M-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

Remon 1 Page 14

DEC 20 1 18 PM '93

*David B. Guthrie*  
REGISTER OF DEEDS  
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David B. Guthrie in a field survey on Sept. 21, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:


- 1839: G.L.O. Survey by Lewis Clason - Set Post and referenced Hem. 14 - N53°W - 33 / Y. Pine 16 - S79°W - 41
- 1903: County Survey by Edw. Chappelle Sr. Set N.B.T. - W. Pine Stp. - N8-1/2E - 46
- 1947: Survey by Robert S. Scott for the Plat of Pine Grove Shores.
- 1975: Surveys by Robert H. Paquette and David B. Guthrie - Found 1/2" Iron Rod.
- 1988: Survey by David B. Guthrie - Found 1/2" Iron Rod.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Found Nail placed above 1/2" Iron Rod.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993: Set 1/2" x 24" Iron Rod with a 3" brass cap stamped to identify the corner. Referenced -  
West - 28" White Pine - 35.45 Feet  
S48°W - Utility Pole - 44.97 Feet  
S55°E - 32" Oak - 33.24 Feet  
N65°E - 20" Oak - 53.80 Feet  
West - Concrete Monument - 33.00 Feet



Signed by *D.B. Guthrie* Date 12-20  
Surveyor's Michigan License No. 22435