

1993 Alcona County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>28N</u> R <u>7E</u>	<u>M - 10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David B. Guthrie in a field survey on August 25, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: G.L.O. Survey by Lewis Clason - Set post and referenced Cedar 5 - S51 $\frac{1}{2}$ °W - 27 / W.Birch 12 - N26°E - 13
 1965: Survey by John C. Miller for the Plat of Shafer's Sunset View
 1987: Survey by David B. Guthrie - Reset corner from the Plat of Shafer's Sunset View and referenced. Set 1/2" Iron Rod.
 1990: Survey by David B. Guthrie - Found 1/2" Iron Rod and verified previous references.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1993: Found 1/2" Iron Rod placed by Thomas F. Fabis

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: Set 1/2" x 24" Iron Rod with a 3" aluminum cap stamped to identify the corner.

Referenced:

- S65°E - NWly Cor.Hse. - 63.02 Feet
 S28°E - SWly Cor.Hse. - 78.25 Feet
 North - 5" Cedar - 42.63 Feet
 N20°W - 5" Cedar Stump - 38.76 Feet

RECORDED

Remon 1 Page 16

Dec 20 1 18 PM '93

Janis A. Brantley
 REGISTER OF DEEDS
 ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by *D.B. Guthrie* Date 12-22
 Surveyor's Michigan License No. 22435

