

**2000 Alcona County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>8E</u>	<u>C-5</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Alcona County
Remonumentation
Liber 2 Page 57

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 09-20-2000 At 09:36 am.
LAND CORNER 9.00

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on April 7, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: GLO Survey by Thos. Pattison Set section corner Referenced: Cedar 10-N26°W-14/Tamarack 14-S36°E-20
- 1993: Feb. Survey by Duane R. MacNeil Found rerod
- 1993: March Survey by Duane R. MacNeil Found survey iron
- 1995: Survey by Earl T. Lewis Found railroad spike 3.9' South of centerline. Referenced: S45°E-43.63'-fence post/ N55°E-139.65'-power pole/N55°W-104.62'-power pole/S45°W-95.40'-8" ash

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found railroad spike flush centerline road N & S 3.5' South of centerline at approximate P.I. (centerline extended E + W). Replaced with 1/2" rebar.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2000: Placed 3" Alcona County cap stamped to identify the corner over 1/2" iron rod in monument box.
Referenced:

- Found tag #27452 in 8" elm-S46°W-95.42'
- Found tag #27452 in power pole-N51°W-104.52'
- Set tag in fence post-S45°E-49.70'
- Found tag #27452 in power pole-N50°W-139.56'

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Date 9-6-2000
County Rep. D. T. Kibbe

Signed by _____
Surveyor's Michigan License No. 37278



Date September 15, 2000

FORM APPROVED BY MICHIGAN STATE BOARD OF

PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1993
REVISED OCT., 1995

**SURVEY &
REMONUMENTATION**

FEB 07 2001

SECTION