

SURVEY & REMONUMENTATION

RECORDED

1994 Alcona County Remonumentation Corner

Nov 7 2 08 PM '94

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

David A. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Alcona
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>28N</u> R <u>8E</u> | <u>D-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Alcona County
Remonumentation
Liber 1 Page 67

E.J.L.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3				●								
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David B. Guthrie in a field survey on May 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840: G.L.O. Survey by Thos. Pattison - Set post and referenced Hemlock 10 - S35E - 10 / Hemlock 10 - N25W - 15

1981: Survey by D.R. MacNeill and Associates


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found P.K. Nail at the intersection of the center of Spruce Road, a fence line North and School Road South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994: Replaced with a 5/8" Iron Rod with a 3" Brass Cap stamped to identify the corner placed in a Monument Box.
Referenced -

- North - Fence Corner Post - 30.10 feet
- S26°E - Fence Corner Post - 56.82 feet
- N25°W - Ely. Gate Post - 47.78 feet
- S55°W - Utility Pole - 87.82 feet



Signed by *David B. Guthrie*

Date Nov. 5, 1994

Surveyor's Michigan License No. 22435