

SURVEY & REMONUMENTATION

1994 Alcona County Remonumentation Corner
APR 25 1995

Alcona County
Remonumentation
Liber 1 Page 76

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

RECORDED

<u>Alcona</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>28N</u> R <u>8E</u>	<u>L-3</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

DEC 9 10 33 AM '94

Janis A. Battison
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

E.T.L.
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	5		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, David B. Guthrie in a field survey on June 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840: G.L.C. Survey by Thos. Battison - Set post and referenced Sugar 14 - N35E - 18 / Beech 6 - S10W - 26

1907: Survey by Edward Chappelle - Dark Gray Boulder 18"x21"

1979: Survey by David B. Guthrie - Found Nail

1982: Survey by David B. Guthrie - Found Nail

1983: Survey by David B. Guthrie - Found Nail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 1/2" Iron Rod

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994: Replaced with a 5/8" Iron Rod with a 3" Brass Cap stamped to identify the corner placed in a Monument Box.

Referenced -

- S23°E - 15" Maple - 37.94 feet
- S17°W - 12" Pine - 76.78 feet
- N08°E - Utility Pole - 64.34 feet
- N03°W - 28" Maple - 102.85 feet



Signed by David B. Guthrie

Date Dec. 9, 1994

Surveyor's Michigan License No. 22435