

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County
 Remonumentation
 Liber 217
 Page RECORDED

For corners in Alcona (County) Located In: Corner Code # or

1. Public Land Survey	T 28N R 8E	M-8
	T 28N R 9E	A-8
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	

APPROVED LAND CORNER
 P.A. 345 of 1990
 ALCONA COUNTY
 Date: 11-21-96
 County Rep: E.T.K.

Nov 21 1 51 PM '96

Doris A. Hamilton
 REGISTER OF DEEDS
 SECOND FLOOR, COURTHOUSE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	6	5	4	3	2						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Daniel T. Kibbe, in a field survey on June 20, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: G.L.O. Survey by Lewis Clason - set post & referenced: Beech 12 - S 30 1/2 W - 26 / S. Maple 12 - N 60 1/2 W - 22.
- 1907: Edward Chapelle - N.B.T.
- 1983: Survey by Dave Guthrie - referenced existing iron rod.
- 1994: MDOT F-41 Alignment by Cliff Lindgren - referenced 1/2" rerod.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 1/2" rebar in C/L F-41, 0.2' under surface.

This corner position is compatible with local surveys and agrees with MDOT records. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed 3" Alcona County cap stamped to identify the corner over 1/2" iron rod in monument box.

- Referenced:
- S 73° E - 52.05' - fd. MDOT N/Tag in 9" Spruce
 - S 53° W - 74.58' - fd. MDOT N/Tag in 18" Poplar
 - N 82° W - 43.35' - fd. MDOT N/Tag in Power Pole
 - S 47° E - 112.80' - NW corner block house foundation



Signed by *Daniel T. Kibbe*

Date October 16, 1996

Surveyor's Michigan License No. 37278

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

REMONUMENTATION

DEC 16 1996
 COMMISSION